Improving and extending Rampur Channel, Nanjangud Taluk, Mysor.

Statement showing the approximate quantities of work in each contract.

	Per	No. 2 Contract Section. 0 to 1st Mile.	No. 3 Contract Section. 1st to 3rd Mile.	No. 4 Contract Section. 3rd to 5th Mile.	No. 5 Contract Section. 5th to 6th Mile.	No. 6 Contract Section. 6th to 7th Mile.	No. 7 Contract Section. 7th to 8¼ Mile.	No. 8 Contract Section. 8¼ to 9th Mile.	No. 9 Contract Section. 9 to 9½ Mile.	No. 10 Contract Section. 9½ to 10th Mile.	No. 11 Contract Section. 10 to 12th Mile.	No. 12 Contract Section. 12th to 14th Mile.	No. 13 Contract Section. 14 to 15th Mile.	No. 14 Contract Section. 15 to 17½ Mile.	No. 15 Contract Section. 17½ to 20¼ Mile.	No. 16 Contract Section. 20¼ to 22nd mile.	No. 17 Contract Section bridges. 0 to 22nd Mile.
Excavation	C. yd.	45,422	48,814	2,27,484	27,306	23,558	19,057	8,130	12,578	10,599	26,749	34,247	17,966	17,526	38,685	24,282	3,411
Stone in surki mortar	C. ft.	4,371	...	...	...	...	...	...	...	...	...	...	...	...	...	5,300	16,940
Cut stone in do	Do	1,301	...	...	...	...	...	...	...	...	...	...	...	...	...	294	...
Brick in do	Do	4,622	1,188	10,804	1,188	11·88	1,980	396	396	3·96	2,772	2,376	1,584	2,887	2,772	1,647	399
Do archwork do	Do	703	...	...	...	...	...	...	...	...	...	...	...	12	...	8,409	...
Pointing with surki mortar	Sqr.	14·30	...	...	...	...	...	...	...	...	...	...	...	0·45	...	5·98	42·24
Plastering with do	Do	34·96	5·92	13·56	3·84	3·84	6·40	1·28	1·28	1·28	8·96	7·68	5·12	9·65	8·96	225·59	11·02
Surki concrete	C. ft.	469	...	126	...	...	...	...	...	...	...	80	...	118	...	4,342	3,790
Slab stones	Do	667	68	22	9	9	153	3	3	3	61	18	12	45	21	3,534	1,524
Corder work	R. ft.	250	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Earthwork	C. yd.	320	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Teak wood beams	C. ft.	66	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Rough stone revetment	C. yd.	101	...	574	...	...	...	...	...	...	...	623	...	540	...	93	...
Shutters for head and scouring sluices (3'—7' × 5'—10')	Each.	7	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Repairs and improvements to waste weirs, &c., will be paid at tendered rates. Quantity of work as may be required	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Carriage of iron pipes and fixing	Each.	3	9	14	6	6	10	2	4	2	14	14	12	12	18	4	...
Brick in mortar	C. ft.	..	344	...	...	...	1,727	...	...	...	238	904	...	1,448	...	...	...
Stone in mortar	Do	...	227	...	...	...	...	...	...	...	150	...	...	...	...	...	...
Plastering with mortar	Sqr.	...	...	...	...	...	11·08	...	...	...	1·35	4·58	...	7·36	...	...	...
Shutters (5½' × 7')	Each.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Embankment including consolidation	C. ft.	...	...	...	...	...	1	...	...	...	...	4,098	2,116	17,363	...	...	...
Shutters with iron work complete (2½ × 1½)	Each.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Cut stone in mortar	C. ft.	...	...	...	...	...	...	...	...	...	...	...	...	15	...	...	...
Centerings	Each.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Cornice work	C. ft.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1,669	...
	L. S.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	about (2,000)	...
	R. ft.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	about (3,000)	...
Approaches	C. yd.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1,347
Benching rock	C. ft.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	40
Pillars, beams and carbel stones	Do	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Metalling and gravelling	C. yd.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...

Note.—General repairs and improvements, rough stone work, old and new, to weirs, silt dams, aprons and revetments to be executed where required must be tendered for at per cubic yard.

Alternative rates for masonry works in ordinary mortar and in surki mortar to be tendered.

G. H. BAYLY,
Executive Engineer.

493